

N. VALAVANARASU CONSTRUCTIONS

No. 11/1, Venkateswara Colony 2nd Street, Kodungaiyur, Chennai 600 118

E Mail Id: valavanarasu@gmail.com

Date: 16-06-2019

ESTIMATE FOR SISTERS KITCHEN RENOVATION WORKS IN OLD AGE HOME AT NO; 50, SUNDRAM STREET, VYASARPADI, CHENNAI. FOR DON BOSCO BEATITUDES

1. Removing the existing wall and floor tiles

1x30'6"x12'0"	366.00	
1x21'3"x4'0"	85.00	
3x12'0"x4'0"	144.00	
2x6'0"x4'0"	48.00	
	<u>643.00sft@10/sft</u>	6430.00

2. Supply and fixing of floor and wall tiles

in position (tile cost 30/sft)

wall

2x21'3"x4'0"	170.00
4x12'0"x4'0"	192.00

Floor

1x30'6"x12'0"	366.00	
	<u>728.00sft@130/sft</u>	94,640.00

3. Applying two coat of Emulsion over one coat of primer for ceiling and inner walls

Ceiling

21'3"x12'0"	255.00
12'0"x9'9"	117.00

Wall	2x21'3"x6'0"	127.50	
	4x12'0"x6'0"	288.00	
	2x9'9"x6'0"	177.00	
Deductions	6x4'0"x3'0"	72.00(-)	
	5x3'0"x7'0"	<u>105.00(-)</u>	
		<u>787.50sft@15/sft</u>	11,812.50

4. Applying two coat of Enamel paint over one coat of primer for Door and Windows

	6x4'0"x3'0"	72.00	
	5x3'0"x7'0"	<u>105.00</u>	
		<u>177.00sft@20/sft</u>	3,540.00

5. Cupboards painting works LS 2,000.00
6. Floor cleaning with soap oil LS 2,000.00

TOTAL	<u>1,20422.50</u>
SAY	1,20,000.00

(RUPEES ONE LAKH TWENTY THOUSAND ONLY)

N. VALAVANARASU CONSTRUCTIONS
 No.11/1, Venkateshwara Colony,
 2nd Street, Kodungaiyur, Chennai-118.

S. A. MD IMRAN

15, AMBERDKAR STREET, PERAMBUR,
CHENNAI - 600 011.
PHONE: 044 - 25370149, 98419 51932

Date: 13/06/19

To


Dear Sir

With reference to your enquiry regarding your requirement of **250 LITERS OF RO PALNT** for Mineral water needs.

We are pleased to enclose herewith our offer for **250 Liters of Ro Palnt** for your kind consideration.

We hope your would find our offer in line with your requirement. Please feel free to call us for further clarifications.

Thanks & Regards



S. A. MOHAMED EMRAAN

S.A. MD IMRAN

SCOPE OF SUPPLY 250 LPH O

RAW WATER PUMP

No of Pump	:	1 Nos
Make of Pump	:	Leader
Hp	:	0.25 Hp
Flow rate	:	2500

VESSELS

No of Vessels	:	2 Nos
Make of Company	:	Pentair
Dimension of Vessel	:	Dia - 12 Inch. Height - 48 Inch
Model of Vessel	:	Cylinders

MICRON FILTERS

No of Micron	:	1 nos
Size of Micron	:	5 Micron
Dimension	:	Slim

HIGH PRESSURE PUMP

Make of Company	:	Lubi
Model	:	Cylindrical, High Pressure
Made of	:	Stainless Steel

RO MEMBRANE

No of membrane	:	1 Nos
Make of Membrane	:	Flimtech / Drew
Model	:	4040
Water	:	Brackish Water
Feed Water	:	2500 LPH
Product Water Supply	:	250 LPH
Reject Water Supply	:	800 LPH

PRICE FOR ABOVE SYSTEM	:	Rs. 1,25,000.00/-
------------------------	---	-------------------

S. A. MD IMRAN

15, AMBERDKAR STREET, PERAMBUR,
CHENNAI - 600 011.
PHONE: 044 - 25370149, 98419 51932

Date: 26/06/2019

To


Dear Sir

With reference to your enquiry regarding your requirement of PUMP AND PLUMBING WORK for water needs.

We are pleased to enclose herewith our offer for **service** for your kind consideration.

We hope you would find our offer in line with your requirement. Please feel free to call us for further clarifications.

Thanks & Regards



S. A. MD IMRAN

S. A. MD IMRAN

PUMP MATERIAL

No of Motor	:	1 Nos
Make of Pump	:	Ramesh
HP	:	3 HP
Phase	:	3 Phase
Model	:	Subermisble
Depth of discharge from Sump	:	300 Feet
Flow Rate per hour	:	15000 Litres
PRICE FOR ABOVE MOTOR	:	Rs,21,050.00

PANEL BOARD

No Of Panel Board	:	1 Nos
Make Of Board	:	Wellon
Phase	:	3 Phase
Hp	:	3 HP
Dry Run Prevert	:	On
System Model-	:	Conduct And Relax
MCB	:	1 Nos
ELCB	:	1 Nos
PRICE OF ABOVE MATERIALS	:	Rs.12,100.00
TOTAL AMOUNT	:	Rs.33,150.00

N. VALAVANARASU CONSTRUCTIONS

No. 11/1, Venkateswara Colony 2nd Street, Kodungaiyur, Chennai 600 118
E Mail Id: valavanarasu@gmail.com

Date: 16-06-2019

ESTIMATE FOR [REDACTED] KITCHEN RENOVATION WORKS IN OLD AGE HOME AT NO; 50, SUNDRAM STREET, VYASARPADI, CHENNAI. FOR DON BOSCO BEATITUDES

1. Labour for Removing the existing cement AC sheets In [REDACTED] kitchen 67'0"x15'0"	<u>1005.00sft@5/sft</u>	5,025.00
2. Supply and fixing of GI Sheet for [REDACTED] kitchen Including purlins and necessary fittings ect... 67'0"x15'0"	<u>1005.00sft@85/sft</u>	85,425.00
	TOTAL	90,450.00
	SAY	90,000.00

(RUPEES NINETY THOUSAND ONLY)

N. VALAVANARASU CONSTRUCTIONS
No. 11/1, Venkateswara Colony,
2nd Street, Kodungaiyur, Chennai-118.

S.K.SURGICAL ENGINEERING CO.,

Manufacture of: Hospital Steel Furniture and Theater Equipment's,
All types of S.S Fabrication Works.

No. 64, Jupiter Street, Mathiyazhagan Nagar, Padi, Chennai - 600 050.
Mukesh Cell No. 9840346494 / 044-26251967,

SUB QUOTATION

Date : 26.06.2019

To,

DON BOSCO BEATITUDES SOCIAL WELFARE CENTRE

No.50, Sundara, Nagappan Street,
Vyasarpadi,
Chennai - 600 039.

S.No	Description of Product	Rate	Qty	GST	Amount
1.	2 Burner Dosa, Chappathi Commercial, contains 304 Grade sheet top 16 gage, Panel 20 gage SS Sheet size 3 feet Length, 24' Breath, 34' Height	40,700	1 No	7,326	48,026
2.	One Single Burner Complete SS 304 Grade Water proof 16" Gage sheet Top, 20 Gage sheet Bottom, dull finish size 24" x 24" x 10" Height.	21,830	1No	3,929	25,759
3.	Wall Rack complete S.S 304 grade water proof S.S. Plates and Tumbler stand as per sample given balance needed 3 Nos.	14,997	3 Nos	8,098	53,089
TOTAL					1,26,874

Terms and Conditions:

1. Advance 70%.
2. Delivery Period 2 Weeks.
3. Delivery Paid

Yours Faithfully,



S.K.SURGICAL ENGINEERING CO,

MUKESH